

Tabela robót ziemnych

Linia trasowania: Oś jezdni 3051P

Pikieta początkowa: 5+223.003

Pikieta końcowa: 6+143.900

Pikieta	Powierzchnia wykopu (m2)	Objętość wykopu (m3)	Powierzchnia nasypu (m2)	Objętość nasypu (m3)	Całk. obj. wykopu (m3)	Całk. obj. nasypu (m3)	Całk. obj. netto (m3)
5+223.00	1.33	0.00	0.01	0.00	0.00	0.00	0.00
5+240.00	1.62	25.05	0.07	0.76	25.05	0.76	24.29
5+258.00	0.59	20.00	1.12	10.66	45.05	11.41	33.64
5+280.00	0.74	14.59	0.69	19.91	59.64	31.32	28.32
5+300.00	0.65	13.81	0.57	12.63	73.44	43.95	29.49
5+320.00	0.85	14.97	0.51	10.81	88.41	54.76	33.65
5+348.96	1.42	32.95	0.35	12.35	121.37	67.11	54.25
5+360.00	1.74	17.46	0.32	3.66	138.82	70.78	68.04
5+380.00	2.86	45.95	0.15	4.69	184.77	75.46	109.30
5+400.00	2.31	51.65	0.22	3.69	236.42	79.15	157.27
5+420.00	1.91	42.14	0.28	5.01	278.56	84.16	194.40
5+440.00	1.20	31.06	0.52	8.08	309.62	92.24	217.38
5+460.00	0.47	16.67	0.76	12.86	326.29	105.10	221.19
5+480.00	0.51	9.77	0.95	17.13	336.06	122.23	213.83
5+500.00	0.44	9.46	1.21	21.64	345.52	143.87	201.65
5+520.00	0.61	10.47	1.02	22.36	355.99	166.23	189.76
5+540.00	0.76	13.67	0.59	16.12	369.66	182.35	187.31
5+560.00	1.30	20.52	0.52	11.05	390.18	193.40	196.78
5+580.00	1.41	27.09	0.29	8.03	417.28	201.43	215.85
5+600.00	1.38	27.97	0.35	6.32	445.25	207.75	237.50
5+620.00	1.11	24.94	0.54	8.83	470.19	216.59	253.60
5+640.00	1.00	21.13	0.56	11.03	491.32	227.61	263.70
5+660.00	0.86	18.65	0.60	11.66	509.96	239.27	270.69
5+680.00	0.55	14.11	0.56	11.60	524.07	250.87	273.19
5+700.00	0.66	12.08	0.59	11.52	536.15	262.40	273.75

5+720.00	1.12	17.83	0.46	10.53	553.98	272.93	281.06
5+740.00	0.88	20.05	0.55	10.09	574.04	283.02	291.02
5+760.00	0.61	14.91	1.11	16.57	588.95	299.59	289.36
5+780.00	0.56	11.74	1.61	27.17	600.69	326.76	273.92
5+800.00	0.45	10.12	1.93	35.41	610.80	362.17	248.63
5+820.00	0.34	7.86	1.90	38.31	618.66	400.48	218.18
5+840.00	0.52	8.58	1.39	32.92	627.24	433.41	193.83
5+860.00	0.64	11.63	1.23	26.22	638.87	459.63	179.24
5+880.00	0.65	12.97	1.09	23.22	651.84	482.86	168.99
5+900.00	0.57	12.21	1.05	21.43	664.06	504.29	159.77
5+920.00	0.82	13.86	0.71	17.61	677.92	521.89	156.03
5+940.00	0.95	17.65	0.48	11.87	695.57	533.76	161.81
5+960.00	1.31	22.57	0.31	7.84	718.14	541.60	176.54
5+980.00	2.04	33.47	0.21	5.22	751.60	546.82	204.79
6+000.00	2.21	42.44	0.20	4.18	794.04	550.99	243.05
6+020.00	2.15	43.58	0.21	4.11	837.63	555.11	282.52
6+040.00	2.18	43.27	0.21	4.19	880.89	559.30	321.59
6+060.00	2.46	46.39	0.20	4.14	927.28	563.44	363.84
6+080.00	2.50	49.59	0.23	4.35	976.88	567.80	409.08
6+100.00	3.03	55.32	0.17	4.06	1032.19	571.85	460.34
6+120.00	3.59	66.26	0.06	2.30	1098.45	574.15	524.30
6+143.90	3.97	90.39	0.00	0.66	1188.84	574.81	614.03